



ODYSSEY
MANUFACTURING CO.

QUOTE

From: Andrew Mock, Field Service Sales Manager
To: Chris Jackson City of Lake Wales WWTP
Subject: SODIUM HYPOCHLORITE SYSTEM ANNUAL SERVICE
Date: December 26, 2019

Chris,

Odyssey is pleased to quote you for the replacement of your Sodium Hypochlorite pump skid. As you know you have three prominent "old" style Sigma I pumps rated for 17GPH. This pump has been obsolete for nearly 7 years now and the only components still available for them is the wet end rebuild kit. The existing skid was installed in 2007 and has been repaired multiple times since and is at the end of its life. Pump 3 is not functional and the plumbing for this pump is broken as well. The average life expectancy of PVC in this application is around 10 years so you have gotten your money's worth out of the system. The remaining pumps are old but may still be used if necessary. Odyssey would set up one of your pumps outside and run a temporary feed line to your contact chamber so the chemical room may be stripped and the new skid installed. This will include all new piping within the room only.

(1) Blue Planet triplex Skid built for the Prominent 16.6/17GPH pumps	\$18,000
(3) Prominent Sigma 1 Pumps S1CBH07065PVTS070UD810S1EN01	\$10,008
Lot. Pipe and fittings	\$ 450
Lot. Hardware and Consumables	\$ 150
(8Hrs.) Labor Technician @ \$85/Hr.	\$ 680
(4Hrs.) Labor Electrician	\$ 340
(8Hrs.) Labor Technician Assistant @ \$45/Hr.	\$ 336
Total	\$29,988

Thanks for your consideration. Andrew